

King Charles III England Coast Path – Hunstanton to Sutton Bridge

Contents

Overview of establishment of the King Charles III England Coast Path

- Part 1 Trail Overview
- Part 2 Protected Landscapes
- Part 3 Infrastructure Delivery
- Part 4 Challenges



Subtitle goes here

Trail overview




Stretch 4 – Hunstanton to Sutton Bridge

33 miles (53km) total length


- 27.5 miles within Norfolk however Norfolk County
 Council established the 5.5 miles up to Sutton
 Bridge in Lincolnshire
- Opened 6 March 2024











Subtitle goes here

Protected Landscapes




Designations

The Wash

- RAMSAR
- Special Protection Area (SPA)
- Special Area of Conservation (SAC)
- Site of Special Scientific Interest (SSSI)
- National Nature Reserve

Snettisham Common Land

Norfolk Coast National Landscape







Snettisham RSPB Nature Reserve waterbird refuge

The saltmarsh and mudflats here offer spectacular views, but aren't safe to walk on. The shingle flats are also an important nesting habitat for rare ringed plovers and oyster-catchers.






Waterbirds need their energy to find food, rest and keep warm so stick to the path here to avoid disturbing them.



Please keep dogs on the path and on leads at all times through the reserve.















This is a sensitive conservation site. Keep dogs under close control and stay on the flood bank footpath.













///slogans.dancer.fruity








Interpretation




- Enhanced, creative information installations
- To be installed late January/early February 2025
- More engaging and appealing than typical information boards
- To be installed at Hunstanton, Heacham, Ken Hill, Snettisham
- Important information to help protect the sensitive nature the trail passes through
- Tactile and accessible (includes Braille)





People counters

- People counters installed at Snettisham and Wolferton
- Counters were installed on the top and bottom of bank at Wolferton to check compliance
- Continuing to work to encourage people to keep to the path
- From March to present:
 - Snettisham counter 5248
 - Wolferton (upper and lower banks) - 6626
- Additional counters will be installed further round the path





Subtitle goes here

Infrastructure Delivery



Signage

In total:

30 fingerposts

28 waymarkers

22 'urban fingers' installed along the route











17 field gates (2 in 1 combination gates) and 2 kissing gates installed





Gates

Wolferton

Initial issue:

Steep cross gradient, lack of sufficient width and concrete block over utilities prevented access.

First proposal was to reprofile the bank with a large excavator with material creating an accessible path to walk on.

Natural England HRA: The works will take place between July 1st and October 31st avoid disturbance to the non-breeding bird assemblage and impacts on breeding redshank.






Wolferton

Final concept was a simple approach.

A retaining wall using posts and sleepers was installed. The posts were left high to act as a handrail

This was backfilled with aggregate to create an accessible route







Challenges



Challenges

Consents – Environment Agency, Internal Drainage Board, Landowner

Seasonality of audits – Vegetation/ cattle

Team resource

Promotion









Thank you